

REPORT OF TAKEOFF QUANTITIES FROM CUSTOMCAD FILES

Customer Name :	Custom Home Builder
Job Number :	1501
Job Location :	1234 Foundation Lane

MESSAGES	

CONCRETE VOLUMES	
Yards of Concrete in Footings	11.73
Yards of Concrete in Walls	49.54
Yards of Concrete in Pads	0.93
Yards of Concrete in Iso.Footings	1.00
Yards of Concrete in Piers	
Yards of Concrete	63.20

Footing Totals (Ln.Ft.)	
Sum of LENGTH	
Footing	Total
16 in. X 8 in. Footing	330.33
18 in. X 8 in. Footing	25.67
21 in. X 8 in. Footing	8.33
Grand Total	364.33

Wall Totals (Ln.Ft.)	
Sum of LENGTH	
Wall	Total
8 in. X 9 ft. Wall	134.33
8 in. X 3 ft. Wall	69.00
8 in. X 4 ft. Wall	59.92
8 in. X 5.67 ft. Wall	9.00
8 in. X 5 ft. Wall	30.42
8 in. X 6 ft. Wall	15.67
10 in. X 7 ft. Wall	19.67
10 in. X 9 ft. Wall	6.00
10 in. X 8 ft. Wall	8.33
8 in. X 4.67 ft. Wall	3.00
8 in. X 6.67 ft. Wall	3.00
8 in. X 7 ft. Wall	3.00
8 in. X 8 ft. Wall	3.00
Grand Total	364.33

Ledge Totals (Sq.Ft.)	
Sum of SQ.FT. OF SURFACE	
LEDGES	Total
4 in. Brickledge	396.14
Grand Total	396.14

REPORT OF TAKEOFF QUANTITIES FROM CUSTOMCAD FILES

Customer Name	: Custom Home Builder
Job Number	: 1501
Job Location	: 1234 Foundation Lane

PostPads (Count)	
Sum of QUANTITY	
POSTPADS	Total
30 in. X 30 in. X 12 in. PAD	4
Grand Total	4

Isolated Footings (Ln.Ft.)	
Sum of FTG LENGTH	
ISOLATED FOOTINGS	Total
16 in. X 8 in. Isolated Footing	30.38
Grand Total	30.38

Piers (Count)	
Sum of QUANTITY	
PIERS	Total
Grand Total	